




## Communication and Interaction

- **box** -- Permanent files
  - E\_CF\_Presentation\_MAY6\_v4.ppt
- **Google docs** -- Co-editing
- **facebook** -- Inspire, broadcast + forward




# Inspire, Broadcast + Forward



 **Evelina Widén**  
April 30 at 4:55am

Roof construction

Now I will calculate the cost according to a construction like this. Please let me know the sizes of the timber joists or any other changes.



Like · Comment



# Meeting Protocol

**Dry Run 1**  
 Invite Only · By Claire Frykman

Going (7)  
 Claire Frykman (Host)  
 Flavia Grey  
 Evelina Widén  
 Ben Carter  
 Jackie Yiyang Jiao  
 Alicja Wolniak  
 Kyungki Kim  
 Recent guests (5 new)

Today 2:00pm  
 GoToMeeting

Write Post Add Photo / Video Ask Question  
 Write something...

Flavia Grey  
 1. Please join my meeting, Tuesday, March 11, 2014 at 2:00 PM Pacific Daylight Time.  
<https://global.gotomeeting.com/join/970123437>  
 2. You will be connected to audio using your computer's microphone and speakers (VoIP). A headset is recommended.  
 Meeting ID: 970-123-437

**BrainMerge** ©Stanford University PBL Lab

Voting Room Title: Decision Metrics

Please create category, then drag and drop the ideas into each category.

Add new category


Category	Count	Country
Occupant Health	100	United States
Cost (construction + maintenance)	81	United States
Ease of Reoccupancy after Earthquakes	81	United States
Easy maintenance (i.e. access to MEP room, roof, easy to deliver)	71	United States
Accessible by and attractive to public	61	United States
Biophilic: including elements that nurture human attention to natural processes (Living building challenge)	41	United States
Reducing water/energy demands	51	United States
Constructability	51	Sweden
Keep construction duration requirements	100	United States

Category	Count	Country
Cost (construction + maintenance)	81	United States
Ease of Reoccupancy after Earthquakes	81	United States
Reducing water/energy demands	51	United States
Occupant Health	100	United States
Easy maintenance (i.e. access to MEP room, roof, easy to deliver)	71	United States


Category	Count	Country
Biophilic: including elements that nurture human attention to natural processes (Living building challenge)	41	United States
Easy maintenance (i.e. access to MEP room, roof, easy to deliver)	71	United States

Category	Count	Country
Occupant Health	100	United States
Easy maintenance (i.e. access to MEP room, roof, easy to deliver)	71	United States

# TERF – Online Collaboration




## January - Kickoff



## March – Winter Presentation




February









Late February



## March - Fishbowl



# Decision Matrix



- ◆ Personal Preference
- ◆ Architecture
- ◆ Social Responsibility
- ◆ Economic Prosperity
- ◆ Environmental Stewardship

## Fullfill client goals = Project Success



Karolina

"Innovative, efficient, flexible and sustainable. "

"Make nature penetrate the building, make building "floating""



Michael

"Value on performance after seismic event."

"Emphasize the concept of nature."



Mike


"Statement building"

"Access - a lot of people will need to enter and exit the building."


# Total Value Framework



# Healthy Building




# Total Value Framework



Wellbeing  
Target Value Design (TVD)  
Sustainable Target Value (STV)

# Total Value Framework





# Total Value Framework




Wellbeing




Wellness



# Lake Merced Weather



# Lake Merced Weather



# Earthquake Information




USGS - Provided Output

$S_S = 2.177 \text{ g}$        $S_{HS} = 2.177 \text{ g}$        $S_{DS} = 1.451 \text{ g}$   
 $S_1 = 1.037 \text{ g}$        $S_{H1} = 1.348 \text{ g}$        $S_{D1} = 0.899 \text{ g}$

For information on how the  $S_S$  and  $S_1$  values above have been calculated from probabilistic (risk-targeted) and deterministic ground motions in the direction of maximum horizontal response, please return to the application and select the "2009 NEHRP" building code reference document.

$S_S = 2.177 \text{ g}$   
 $S_{DS} = 1.451 \text{ g}$



<http://geology.com/articles/images/san-andreas-fault-map.jpg>


## Soil Profile




- USGS Soil Type C
- Well sorted fine to medium sand
- Water table: 14ft below grade
- Friction angle = 40 degrees
- $K_a = 0.217$ ,  $K_o = 0.357$ ,  $K_p = 4.599$
- Unit weight = 116 pcf, saturated = 135 pcf

(from Lindeburg, *Civil Engineering Reference Manual for the PE Exam*, 8th ed.)


# Urban Context



# Building Access



## The Fog Catcher






## Fog Harvesting Methods




## Biomimicry – The Cactus




### Water Conservation

- Reduce evaporation
- Provide shade
- Condense moisture for roots

## How it Works




# How it Works



## Karl the Fog

Fog: 0.05 - 0.5 grams of water per  $\text{cm}^3$

1 sq. ft.  $\rightarrow$  0.12 - 0.60 gallons/day




Karl the Fog

Façade → 12,515 gallons/day



# Shape Evolution



## Site Placement








## Site Placement



# Elevations



# Elevations




## Under the Cantilever



## Under the Cantilever



## Under the Cantilever















# Floor Plan - Ground




# Auditorium









## Floor Plan - 2



## Faculty Lounge






## Student Collaboration Space




## Student Collaboration Space



# Sections



NORTH - SOUTH



EAST - WEST

## Structural Floorplan – 2<sup>nd</sup> Floor



Glulam Columns 8"x8"



Steel Column W14x257



L-shape Beams 8"x 6"



Prestressing Cables 2 in<sup>2</sup>



Timber Shear Walls 12"




Steel Shear Walls 12"




Truss System (W18x106 for cantilever, W18x86 for interior beams)




# Architecture



# Structural System






# Timber Floors System





## Decision Matrix - Cantilever

		SE	MEP (STV)	ARCH	CM
Steel		+	-	+	+
CLT Wall		-	+	+	-
Hybrid		+	+/-	-	+/-

# Live Load Requirements

Room Function Type	Total Area (Sq-Ft)	Minimum Live Load (psf)
Faculty Offices	3600	50
Faculty Lounge	1000	100
Student Offices	1200	50
Auditorium	3000	100
Classroom	3600	40
Storage Rooms	1000	150

Based on California Building Code.


[http://www.ecodes.biz/ecodes\\_support/free\\_resources/2013California/13Building/PDFs/Chapter%2016%20-%20Structural%20Design.pdf](http://www.ecodes.biz/ecodes_support/free_resources/2013California/13Building/PDFs/Chapter%2016%20-%20Structural%20Design.pdf)

## Lateral Loads

	Base shear (kips)	Overturning Moment (kip-ft)
Pure shear wall system	7100	135300
Pure BRBF system	2200	42300


From ASCE 7-10

## Truss System Detail




- Vierendeel Truss
  - Beam W18x106
  - Column W14x257

## Load Path




## Load Path




- Gravity Systems
- Lateral Systems


## Truss Detail



- Regular prefabricated modules
- Assembled on site with bolts
- Pre-cambered






## Cable System



- Cable Systems
  - 7-wire strand pre-stressing wires
  - Cross section area =  $2 \text{ in}^2$




## Coordination between SE and Arch




# Roof Solutions

- Traditional roof solution



## Steel Truss

- Assembled while the concrete slab in foundation hardens
- Assembled into 4 pieces, each 40 000 lbs ~ 20 short ton




Mobile Crane 40 ton = \$212hr



- 1 RED = Assembled on ground
- 2 ORANGE = Assembled on ground
- 3 BLUE = Assembled on ground
- 4 TURQUOISE = Assembled on ground

1,2,3,4 are lifted in place and connected



## Truss System Value


### **Value**

- Easy to transport
- Easy to connect
- Reduce stress on the truss
- Safer
- Less expensive
- Architectural freedom


### **How?**

- No site welding
- Assembly method – fewer lifts
- No proprietary connections
- Customized design
- Increased open space


# Timber Floor System



# Timber Floor System




# Timber Slab Design






## Slab to Slab Connection




- Timber slabs “key” together
- Epoxy + Screws for site connections

## Slab to Truss Connection




- Structural Screws in Staggered Pattern

## Slab to Truss Connection




- Structural Screws in Staggered Pattern


# Structural Layout




# Structural Layout



# Cable Connection




# HVAC Design Strategies



40%: Solar gains


50%: Internal gains

## Mini Shafts







# MEP Mini Shafts



# Section View of Mini Shafts




# MEP Integration




Hollow Slabs  Underfloor air distribution plenum

## MEP Integration




Hollow Slabs  Underfloor air distribution plenum

## Under Floor Air Distribution using Timber Slab



# Prefabrication of floor system

- On-site prefabrication
  - Size of site = 130 000 SF
- 56 slabs
  - Two main versions



# Manufacturing plant

Already existing tents on site →



## Time comparison

Steel concrete composite floor

- 35-40 days

Timber slab

- 110 days to manufacture
- 17 days to lift and install

Time saving ~18-23 days



## Cost comparison

Steel concrete composite floor

- ~\$245 000

Prefabricated timber slab incl. Underfloor Air Distribution ductwork

- ~\$290 000

Labour	Material
Carpenter Crew \$63 0000	LVL \$65 000
Finishes \$33 000	CLT \$60 000
HVAC crew \$48 000	Ducts \$12 000

# Timber Slab

## **Added Value**

Faster schedule

Increased quality

Environmentally advantageous

Good seismic performance

## **How?**


Prefabricated units

Integrated MEP and bearing structure

Timber solution

Lightweight

# Structural Floorplan - Groundfloor



## Structural Floorplan – Groundfloor



Glulam Columns 8"x8"



Steel Column W14x257




Timber Shear Walls 12"



Steel Shear Walls 12"

# Lateral Load Systems




## Wall System

- CLT Mass Timber wall


## Frame System

- High Stiffness Wall Equivalent
- Post-tensioning system
- 8.0 sq.in BRB Element

## 3D View of Lateral Systems



## Ground Floor HVAC Solution



## Auditorium

- Heating and cooling
- Versatile connections






## Ground Floor HVAC Solution




# Structural Layout



# Foundations


- Strip Footings



Depth = 2.16 ft  
Width = 7.5 ft


# Foundations

- Strip Footings




## Foundations


- Use Strip Footings as Pile Caps




## Foundations

- Helical Screw Piles
  - No dewatering needed
  - 14" dia. 3-1/2" turbular






## Structural Analysis



Primary Mode	Largest Period
Torsion	0.20 s



## Structural Analysis - Deflections



Points that have largest deflections	Max Deflections (Gravity) - in	Max Deflections (Lateral) -in
A	3.87	1.16
B	1.80	0.96



## Structural Analysis

	Base shear (kips)	Overturning Moment (kip-ft)
Pure shear wall system	7100	135300
Pure BRBF system	2200	42300
ETABS Analysis Results	2800	67000


- Hybrid System

## Balance Stiffness

- Stiffen the shear walls on one side of the building



# BIM Coordination Plan-software




# BIM Coordination Plan-team

- **Early coordination (1-2 weeks)**


- First Architectural REVIT model > REVIT SE > REVIT MEP
- Interdisciplinary discussions for decision making




- **Coordination using shared models**

- Layers
- Dropbox: model sharing
- NAVISWORKS: 4D simulation
- Terf: model walkthrough
- BIM 360 Glue: model integration, clash detection



# Site Access Analysis





-  Usable Access
-  Unusable Access
-  Re-route plan for adjacent facilities

# Site Layout Plan




# Clash Detection-before





# Clash Detection-after

May 7



# Material Access



## Health and safety approach

- Address all risks
  - **RED**; E.g. falling, squeezing and run-over
  - **YELLOW**; E.g. dust, noise and chemicals.
- **YELLOW** most dangerous in long run

- Design for safety
- Fire and safety rounds
- Education;
  - Hand tools, work in elevation, welding, heavy lifting


**Risk Matrix**

	5					
	4	R11	R10	R15	R1	
Probability	3		R3	R8, R12	R2	
	2		R13, R14	R7	R6	
	1					
		1	2	3	4	5
		Consequence				

**"Achieve a healthy building through a  
healthy approach during both the  
design AND the construction"**


# Computer lab schedule

Computer labs - April 27




Construction Start  
September 2019

## Computer Managers Access



Access from N. State Drive  
for Computer Manager

# Computer Managers Entrance




# Zone 1 - Computer labs







# Gantt Schedule



# Milestones



# 4D Construction



A(3)-5(-24) : Roof (16)

# Critical Activities

	Task Mode	Task Name	Duration	Start	Finish	Predecessors	Resource Names
1		Pre-construction	220 days	Tue 19-01-01	Mon 19-11-04		
2		Design	175 days	Tue 19-01-01	Mon 19-09-02		
3		Procurement	140 days	Tue 19-04-23	Mon 19-11-04		
4		Mechanical ventilation procurement	90 days	Tue 19-07-02	Mon 19-11-04	2SS+130 days	
5		Electrical system procurement	80 days	Tue 19-07-16	Mon 19-11-04	2SS+140 days	
6		Prefab floor procurement	70 days	Tue 19-04-23	Mon 19-07-29	2SS+80 days	
7		Construction bearing structure	146 days	Tue 19-09-03	Tue 20-03-24	2	
8		Site work	14 days	Tue 19-09-03	Fri 19-09-20		
9		Site mobilization	8 days	Tue 19-09-03	Thu 19-09-12		Excavation crew B 30
10		Grading	6 days	Fri 19-09-13	Fri 19-09-20	9	Excavation crew B 30
11		Foundation	62 days	Mon 19-09-23	Tue 19-12-17	8	
12		Piles 10 psc.	8 days	Mon 19-09-23	Wed 19-10-02	10	Bearing structure crew piles
13		Strip footings formwork and reinforcement	15 days	Thu 19-10-03	Wed 19-10-23	12	Bearing concrete crew;Water and S
14		Strip footing casting	5 days	Thu 19-10-24	Wed 19-10-30	13	Casting crew
15		Underground MEP and concrete slab works	25 days	Fri 19-11-08	Thu 19-12-12	14FS+6 days	Water and Sewage crew; Bearing concrete crew
16		Casting concrete slab	3 days	Fri 19-12-13	Tue 19-12-17	15	Casting crew
17		Bearing Structure	70 days	Wed 19-12-18	Tue 20-03-24		
18		Prefab trusses on site	9 days	Wed 19-12-18	Mon 19-12-30	16	Casting crew
19		Sheer walls	10 days	Thu 19-12-26	Wed 20-01-08	16FS+6 days	Bearing steel structure
20		Columns	10 days	Thu 19-12-26	Wed 20-01-08	19SS	Bearing steel structure 2
21		Set trusses	4 days	Thu 20-01-09	Tue 20-01-14	19;20;18	Bearing steel structure
22		Prefabricated floors + installation	17 days	Wed 20-01-15	Thu 20-02-06	21	HVAC crew
23		Cable system	10 days	Wed 20-01-15	Tue 20-01-28	22SS	Bearing structure crew
24		Columns 2nd floor	10 days	Wed 20-01-15	Tue 20-01-28	23SS	Bearing steel structure 2
25		Roof	30 days	Wed 20-01-29	Tue 20-03-10		
26		Roof joists and plywood	15 days	Wed 20-01-29	Tue 20-02-18	23;24	Bearing steel structure 2
27		Insulation, vaporbarrier, membrane	15 days	Wed 20-02-19	Tue 20-03-10	26	Bearing structure crew
28		Façade	25 days	Wed 20-02-19	Tue 20-03-24	26	Bearing steel structure 2
29		Ground floor	69 days?	Wed 20-03-25	Mon 20-06-29		
30		Zone 1 GF (MEP + storage)	18 days?	Wed 20-03-25	Fri 20-04-17		
31		Interior walls Zone 1 GF	2 days	Wed 20-03-25	Thu 20-03-26	28	Interior crew
32		Services	13 days?	Fri 20-03-27	Tue 20-04-14		
33		HVAC	13 days?	Fri 20-03-27	Tue 20-04-14		
34		MEP installations	5 days	Fri 20-03-27	Thu 20-04-02	31	HVAC crew
35		Ducting Zone 1 GF	6 days	Fri 20-04-03	Fri 20-04-10	34	HVAC crew
36		HVAC rough in Zone 1 GF	1 day?	Mon 20-04-13	Mon 20-04-13	35	HVAC crew
37		HVAC trim outs Zone 1 GF	1 day?	Tue 20-04-14	Tue 20-04-14	36	HVAC crew
38		Electricity	10 days	Fri 20-03-27	Thu 20-04-09		

GANIT CHART

## TVD Winter Quarter

ESTIMATE AND TARGET VALUE			
WINTER			
	ESTIMATED VALUE	TARGET VALUE	VALUE DELTA
<b>TOTAL</b>	<b>9 260 000</b>	<b>9 800 000</b>	<b>540 000</b>
A Substructure	86 000	710 000	624 000
B Shell	3 400 000	3 330 000	-70 000
C Interiors	1 240 000	1 000 000	-240 000
D Services	3 600 000	3 500 000	-100 000
E Equipment and Furnishing	140 000	160 000	20 000
F Specialty Construction	200 000	330 000	130 000
G Building Sitework	240 000	270 000	30 000
H General Conditions	350 000	470 000	120 000


WINTER ESTIMATE: \$9 260 000

## TVD Spring Quarter


ESTIMATE AND TARGET VALUE			
SPRING	ESTIMATED VALUE	TARGET VALUE	VALUE DELTA
<b>TOTAL</b>	<b>10 650 000</b>	<b>9 800 000</b>	<b>-850 000</b>
A Substructure	260 000	710 000	450 000
B Shell	3 980 000	3 330 000	-650 000
C Interiors	840 000	1 000 000	160 000
D Services	3 020 000	3 530 000	510 000
E Equipment and Furnishing	270 000	160 000	-110 000
F Specialty Construction	200 000	330 000	130 000
G Building Sitework	430 000	270 000	-160 000
H General Conditions	1 660 000	470 000	-1 190 000

**SPRING ESTIMATE: \$10 650 000**

# COST ESTIMATE





# Targets by Cluster





## Building Performance - STV



**LEED**



## Previous Swinerton Challenges



Leapfrog Sustainability



Biomimicry



Native



Sustainable Performance



Sustainable Design and Construction

## Wellbeing – Active Design

- Smoke-free building.
- Stairs, elevators and bathrooms encourage movement.
- Access to take a break or be active.




## Wellbeing - Biophilia

- Reduced stress through views of natural landscapes.
- Increased social interactions and sense of community.
- 10 to 25% better mental function and memory.



## Wellbeing - Auditorium

- Area for relaxation, quiet, socializing, fitness.
- Quiet room with soft music for times of stress.
- Creativity, self-expression, cooperation, exploration.



## Wellbeing - Workspaces

- Opportunity to engage in spontaneous social encounters
- Freedom to move from one social phase to another

- Better ventilation improves productivity by 11%
- Individual temperature control by 3%



## Wellbeing - Daylight

- Increased productivity up to 18%.
- 5-14% Higher Test Scores
- Students learn 20-26% faster





# A Special Thanks to

Renate Fruchter

Karolina Ostrowska, Mike Miller and Michael Seaman

All mentors that supported and inspired our work

*Team Pacific*



## Learning experiences

"Even if you say green and I say green, I'm thinking blue and you're thinking orange."

"Remember to mute your mic/Unmute your mic."

"What drives project success is a strong interest in everyone's ideas that arise during the project."

"Maybe I want to be an architect?" // Structural Engineer

"The social interaction is the best – I love you guys."

"Embrace your differences and take advantage of them"